

**TENDER NOTICE**

|   |  |  |
|---|--|--|
| 1 | Name of The Works                          | Repairing work of wall Putty and Painting, Flooring and I-Beam in Examination Room of school building. |
| 2 | Estimated Area                             | 307 Sq. ft.  |
| 3 | Time of Completion                         | One Month  |
| 4 | Date of Tender Notification                | 18.05.2023   |
| 5 | Last Date/Time for Receipt of Bids         | 25.05.2023   |
| 6 | Name and Address of office Inviting Tender | Principal, DAV Public School, Rotary Campus, Ashok Nagar, Gaya.  |
| 7 | Contact Number of Procurement Office       | 0631-2950279   |
| 8 | Help Numbers                               | 6205946442   |

**Following points need attention**

01. The School shall not be liable to pay any tax, freight, etc. which has not been expressly stipulated in the quotation in the event of acceptance of the quotation. The School will deduct TDS as per rule of Income Tax.
02. The undersigned does not bind him to accept the lowest quotation and reserves the right to accept the quotation in whole or in part i.e., with respect to the entire article mentioned in the attached statement or in respect of one or more than one articles specified in the attached statement as he may decide.
03. On acceptance of the quotation it will become a contract and the contractor shall be bound by the terms and conditions of the quotation as well. Contractor must fulfill the terms and conditions of Government of Bihar as well as govt. of India.
04. The quantity of articles indicated in the attached statement may be increased or decreased at the discretion of the undersigned without assigning any reason.
05. The rates quoted by the contractor shall hold good upto finishing of the renovation works. No amendment will be accepted in the rate of renovation.
06. The description of the said renovation works in details can be had from the office of either RO/Dy. R.O./ARO Bihar Zone- H or from the Principal of DAV Public School, Rotary Campus, Ashok Nagar, Gaya. The payment will be made to the contractor through A/C payee cheque after the finishing of the work and duly approved by the architect.
07. Quotations which do not comply with the above conditions are liable to be rejected.
08. Non-completion of works within the stipulated time, the contractor will be liable to pay penalties as decided by the Building Sub-Committee, except the special circumstances if any.

Principal

Principal  
D.A.V. Public School  
Rotary Campus, Ashok Nagar,  
Gaya (Bihar)



# M/S HAPPY AND ASSOCIATES

ARCHITECTS, ENGINEERS, INTERIOR DESIGNERS

Add:- Near Hindustan Press, Cotton Mill, Gaya - 823001 (Bihar)

Mob. No. 7735269750, 720467722 / Email : happyandassociates@gmail.com, Website : www.happysgroup.com

## ABSTRACT OF COST FOR WALL PUTTY AND PAINTING, FLOORING AND I-BEAM IN EXAMINATION ROOM AT D.A.V PUBLIC SCHOOL, ROTARY CAMPUS, GAYA

Ref no

Date 15/05/2023

| Serial | SoR       | Particulars   | Quantity | Rate   | Unit | Amount |
|--------|-----------|---|----------|--------|------|--------|
|        |           | AREA (19'8" X 15'6")  | 307.0    |        | SQFT |        |
|        |           | I-BEAM  |          |        |      |        |
| 1      | mtr       | Providing and fixing in place an I-beam or Girder for supporting the ceiling as required (Labour charges included)  |          | lumsun |      |        |
|        |           | INTERIOR PAINTING AND FINISH (INCLUDING WALL, CEILING AND BEAM)   |          |        |      |        |
| 2      | 13.74     | Removing white or colour wash by scrapping and sand paper in and preparing the surface smooth including necessary repair scratches etc. complete  | 109.0    |        | sqm  |        |
| 3      | 13.80 A.1 | Providing and applying white cement based putty of average thickness 1 mm. of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.   | 109      |        | sqm  |        |
| 4      | 13.46.1   | Finishing with De'uxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications. Two or more coats applied on walls @ 1.25 ltr/10 sqm. over and including one coat of special primer applied @ 0.75 ltr/10 sqm.   | 109      |        | SqM  |        |
|        |           | FLOOR TILES   |          |        |      |        |
| 5      | 11.38     | Providing and laying Ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such shades except white, Ivory, Grey, Fume Red, Brown, laid on 20 mm thick Cement mortar 1:4 (1 cement: 4 coarse sand) including pointing the joints with white cement and matching pigment etc., complete. | 28.5     |        | Sq m |        |
|        |           | TOTAL   |          |        |      |        |

Note :  
Rates are inclusive of C.S.T.