

TENDER NOTICE

1	Name of The Works	Repairing work of water proofing of pitched (Slope) roof of school building.
2	Estimated Area	601.1 Sq. ft.
3	Time of Completion	Three weeks
4	Date of Tender Notification	11.01.2023
5	Last Date/Time for Receipt of Bids	18.01.2023
6	Name and Address of office Inviting Tender	Principal, DAV Public School, Rotary Campus, Ashok Nagar, Gaya.
7	Contact Number of Procurement Office	0631-2225254
8	Help Numbers	6205946442

Following points need attention

1. The School shall not be liable to pay any tax, freight, etc. which has not been expressly stipulated in the quotation in the event of acceptance of the quotation. The School will deduct TDS as per rule of Income Tax.
2. The undersigned does not bind him to accept the lowest quotation and reserves the right to accept the quotation in whole or in part i.e., with respect to the entire article mentioned in the attached statement or in respect of one or more than one articles specified in the attached statement as he may decide.
3. On acceptance of the quotation it will become a contract and the contractor shall be bound by the terms and conditions of the quotation as well. Contractor must fulfill the terms and conditions of Government of Bihar as well as govt. of India.
4. The quantity of articles indicated in the attached statement may be increased or decreased at the discretion of the undersigned without assigning any reason.
5. The rates quoted by the contractor shall hold good upto finishing of the renovation works. No amendment will be accepted in the rate of renovation.
6. The description of the said renovation works in details can be had from the office of either RO/Dy. R.O./ARO Bihar Zone- H or from the Principal of DAV Public School, Rotary Campus, Ashok Nagar, Gaya. The payment will be made to the contractor through A/C payee cheque after the finishing of the work and duly approved by the architect.
7. Quotations which do not comply with the above conditions are liable to be rejected.
8. Non-completion of works within the stipulated time, the contractor will be liable to pay penalties as decided by the Building Sub-Committee, except the special circumstances if any.

11/01/23
Principal

Principal
D.A.V. Public School
Rotary Campus, Ashok Nagar
Gaya (Bihar)

**ABSTRACT OF COST FOR WATER PROOFING OF PITCHED (SLOPE) ROOF AT D.A.V ROTARY, GAYA,
BIHAR**

Serial	SoR	Particulars	Quantity	Rate	Unit	Amount
		AREA OF PITCHED (SLOPE) ROOF	6,468.0		SQFT	
1	N A	Chieseling of Top Surface of roof Terrace	601.1		Sq m	
2	22.22A	Providing and applying fibre reinforced elastomeric liquid water proofing membrane with resilient acrylic polymers having Sun Reflectivity Index (SRI) of 105 on top of concrete roof in three coats @10.76 litre/ 10 sqm. One coat of self-priming of elastomeric waterproofing liquid (dilution with water in the ratio of 3:1) and two coats of undiluted elastomeric waterproofing liquid (dry film thickness of complete application/system not less than 500 microns). The operation shall be carried out after scrapping and properly cleaning the surface to remove loose particles with wire brushes, complete in all respect as per the direction of Engineer-in-Charge.	601.1		sqm	
TOTAL						