

TENDER NOTICE

1	Name of The Works	Repairing work of converting store and toilet beside examination room into kitchen of school building.
2	Estimated Area	80 Sq. ft.
3	Time of Completion	One Month
4	Date of Tender Notification	18.05.2023
5	Last Date/Time for Receipt of Bids	25.05.2023
6	Name and Address of office Inviting Tender	Principal, DAV Public School, Rotary Campus, Ashok Nagar, Gaya.
7	Contact Number of Procurement Office	0631-2950279
8	Help Numbers	6205946442

Following points need attention

01. The School shall not be liable to pay any tax, freight, etc. which has not been expressly stipulated in the quotation in the event of acceptance of the quotation. The School will deduct TDS as per rule of Income Tax.
02. The undersigned does not bind him to accept the lowest quotation and reserves the right to accept the quotation in whole or in part i.e., with respect to the entire article mentioned in the attached
03. Statement or in respect of one or more than one articles specified in the attached statement as he may decide.
04. On acceptance of the quotation it will become a contract and the contractor shall be bound by the terms and conditions of the quotation as well. Contractor must fulfill the terms and conditions of Government of Bihar as well as govt. of India.
05. The quantity of articles indicated in the attached statement may be increased or decreased at the discretion of the undersigned without assigning any reason.
06. The rates quoted by the contractor shall hold good upto finishing of the renovation works. No amendment will be accepted in the rate of renovation.
07. The description of the said renovation works in details can be had from the office of either RO/Dy. R.O./ARO Bihar Zone- H or from the Principal of DAV Public School, Rotary Campus, Ashok Nagar, Gaya. The payment will be made to the contractor through A/C payee cheque after the finishing of the work and duly approved by the architect.
08. Quotations which do not comply with the above conditions are liable to be rejected.
09. Non-completion of works within the stipulated time, the contractor will be liable to pay penalties as decided by the Building Sub-Committee, except the special circumstances if any.

18/05/23
Principal

Principal
D.A.V. Public School
Rotary Campus, Ashok Nagar,
Gaya (Bihar)

ABSTRACT OF ESTIMATE FOR CONVERTING STORE AND TOILET BESIDE EXAMINATION ROOM INTO KITCHEN
AT DAV PUBLIC SCHOOL , ROTARY CAMPUS, GAYA

Ref no .

Date 15/05/2023

Serial	SoR	Particulars	Quantity	Rate	Unit	Amount
		DISMANTLING EXISTING STORE AND TOILET MAKING NEW OPENING FOR DOOR				
1	NA	Toilet tiles, fixtures and plumbing dismantling			lumsun	
2		wall demolition			lumsun	
3	14.85	Taking out existing wooden door shutter, repair by cutting, painting etc. and refixing of repaired door shutters to existing door frames, including replacement of hinges with screws, etc. as required,	2.0		each	
		KITCHEN CONSTRUCTION (10' X 8')				
4	6.1.12B	Brick work with bricks of class designation 100B in foundations and plinth in :Cement mortar 1:4 (1 cement: 4 coarse sand)				
	6.3B	Extra for Brick work in superstructure above plinth level upto floor V			cum	
		(CLOSING UP OLD OPENINGS)	1.0			
5	5.9.3	Centring and shuttering including strutting,propping etc. and removal of form for slab construction.	1.4		Sq m	
6	5.22.1E	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete.Mild steel.8 mm Dia	46.2		kg	
7	13.11.4	12 mm (1:6) cement Plaster (Toilet wall)	40.1		Sq m	
8	11.38	Providing and laying Ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacturer) of ist quality conforming to IS : 15622 of approved make in colours such shades except white , Ivory , Grey , Fume Red , Brown , laid on 20 mm thick Cement motar 1:4 (1 cement: 4 coarse sand) including pointing the joints with white cement and matching pigment etc., complete.	7.4		Sq m	

9	11.36	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS : 15622 (Thickness to be specified by the manufacture) of approved make in all colours, shades except burgundy , bottle green , black of any size as approved by Engineer-in-charge in skirting , risers of steps and dados over 12 mm thick bed of cement Mortar 1:3(1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm including pointing in white cement mixed with pigment of matching shade complete. (7" HIGH)	23.4		Sq m	
10	13.78.1	Providing one coat of cement primer of approved brand and manufacture on wall surface all complete	24.1		Sq m	
11	13.79.1	Providing water proof cement paint of approved brand and manufacture and of required shade to give and even shade three or more coat on new work all complete			Sq m	
12	8.2.2.2	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations, of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4. Granite of any colour and shade (ON KITCHEN COUNTER TOP)	3.3		Sq m	
13	9.23A.1.	Providing and fixing 25 mm thick shutters for cupboards etc.including black enamelled M.S. butt hinges with necessary screws: Second class teak wood	3.5		sqm	
14	9.23	Extra for providing lipping with 2nd class teak wood battens 25 mm minimum depth on all edges of shutters (overall area of door shutter to be measured)	1.0		sqm	
15	N A	Door	1.0		Each	
16	17.10.1.2	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink painting of fittings and brackets, cutting and making good the walls wherever required :510x1040 mm bowl depth 225 mm	1.0		Each	
17	N A	electrical works and fixtures	LUMSUM			
18	18.3.3	Providing and fixing Polyethelene-Aluminium-Polyethelene (PE-ALPE) Composite Pressure Pipes conforming to IS - 15450, including all special fittings of composite materials 2025 (25 mm OD) pipe	30.0		metre	
19	N A	Plumbing and other fixture installations like nozzle, taps etc along with inlet outlet (labour charges included)	LUMSUM			
			GRAND TOTAL			

SAY TOTAL =

Note:
Rate are inclusive of GST