


## TENDER NOTICE

REF: NO. DAV/RC, AN/GAYA/2024/60

Dated 07/05/20024

1	Name of The Works	Repair and exterior paint work of the rear side of old building
2	Estimated Area	1. Repairing work of rear side of old building 2. Exterior painting of the rear side of old building (Area 12084.23 SFT)
3	Time of Completion	30 days
4	Date of Tender Notification	07/05/2024
5	Last Date/Time for Receipt of Bids	15/05/2024
6	Name and Address of office Inviting Tender	Principal, DAV Public School, Rotary Campus, Ashok Nagar, Gaya.
7	Contact Number of Procurement Office	0631-2950279
8	Help Numbers	9425835417

1. The School shall not be liable to pay any tax, freight, etc. which has not been expressly stipulated in the quotation in the event of acceptance of the quotation. The School will deduct TDS as per rule of Income Tax.
2. The undersigned does not bind him to accept the lowest quotation and reserves the right to accept the quotation in whole or in part i.e., with respect to the entire article mentioned in the attached statement or in respect of one or more than one articles specified in the attached statement as he may decide.
3. On acceptance of the quotation it will become a contract and the contractor shall be bound by the terms and conditions of the quotation as well. Contractor must fulfill the terms and conditions of Government of Bihar as well as govt. of India.
4. The quantity of articles indicated in the attached statement may be increased or decreased at the discretion of the undersigned without assigning any reason.
5. The rates quoted by the contractor shall hold good upto finishing of the renovation works. No amendment will be accepted in the rate of renovation.
6. The description of the said renovation works in details can be had from the office of either RO/Dy. R.O./ARO Bihar Zone- H or from the Principal of DAV Public School, Rotary Campus, Ashok Nagar, Gaya. The payment will be made to the contractor through A/C payee cheque after the finishing of the work and duly approved by the architect.
7. Quotations which do not comply with the above conditions are liable to be rejected.
8. Non-completion of works within the stipulated time, the contractor will be liable to pay penalties as decided by the Building Sub-Committee, except the special circumstances if any.

  
(PRINCIPAL)  
**Principal**  
**D.A.V. Public School**  
(Affi. No - 330065, Sch. No - 65861)  
Rotary Campus, Ashok Nagar

		(1) REAR SIDE OF OLD BLOCKS, ETC.	Qty.	Unit.
(A) REPAIR WORK				
i. Final Area and quantity of repairs work will be measured and calculated on the basis of repairs				
<b>SECTION- I ( DISMANTLING WORK)</b>				
1	15.3	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metres lead:		
<b>SECTION- II ( REPAIR WORK)</b>				
2	14.1	Repair to plasters of thickness 12 mm to 20 mm in patches of area 2.5 sq. metres and under, including cutting the patch in proper shape, racking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.	6.13	Cum
	14.1.1	With cement mortar 1:4 (1 cement: 4 fine sand)		
3	14.72	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. Tube 1.5 m centre to centre horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube chollies, M.S. clamps and MS. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc. wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in-charge. The elevational area of the scaffolding shall be measured for payment purpose The payment will be made once irrespective of duration of scaffolding.	170.00	Sqm
		Note:- This item to be used for maintenance work judiciously, necessary deduction for scaffolding in the existing item to be done.	753.07	Sqm
<b>SECTION- III ( STEEL WORK)</b>				

Sl.No.	S.O.R.	DESCRIPTION	Qty.	Unit.
4	10.2	Structural steel work riveted or bolted in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	600.00	Kg
		<b>SECTION- IV ( FINISHING WORK)</b>		
5	13.82	Painting with ready mixed paint of approved brand and manufacture in all shades to give an even shade:		
	13.82.1	New steel work (two or more coats)	122.55	Sqm
		<b>SECTION- V ( MISCELLANEOUS WORK)</b>		
6	MR	Miscellaneous work expences during repairs and painting etc. complete as per direction of Engineer-in-charge.	LS	
		TOTAL		
		ROUNDUP		

**Note:-** M.S. window sun shade will be made with 1 mm thick M.S. sheet and 25x25x3mm M.S. angle fixed in wall. Sun shade will be painted. Sun shade will be fixed inclined in 2'-6"width in dism: portion and in approx length of 255'-0" at ground & first floor.

		DESCRIPTION	Qty.	Unit.
		(1) OLD BLOCKS ( REAR SIDE AREA)		
		(A) REAR SIDE EXTERIOR PAINTING		
		i. Area of exterior painting = 12084.23 Sft (1123.07 Sqm)		
		<b>SECTION- I ( FINISHING WORK)</b>		
1	14.67	Finishing walls with Premium Acrylic smooth exterior paint with Silicone additives of required shade. (with Asian paints)		
	14.67.1	Old work(Two or more coat applied@ 1.43 ltr/10sqm over existing cement paint surface	1123.07	Sqm
2	13.74	Removing white or colour wash by scrapping and sand paper in and preparing the surface smooth including necessary repair scratches etc. complete.	1123.07	Sqm
		TOTAL		
		ROUNDUP		
		Cost of exterior painting per sqft.		