

TENDER NOTICE

1	Name of The Works	Slope Construction at ground floor of the school.
2	Estimated Area	48 sq. ft.
3	Time of Completion	One week
4	Date of Tender Notification	19.08.2023
5	Last Date/Time for Receipt of Bids	21.08.2023
6	Name and Address of office Inviting Tender	Principal, DAV Public School, Rotary Campus, Ashok Nagar, Gaya.
7	Contact Number of Procurement Office	0631-2950279
8	Help Numbers	6205946442

Following points need attention

01. The School shall not be liable to pay any tax, freight, etc. which has not been expressly stipulated in the quotation in the event of acceptance of the quotation. The School will deduct TDS as per rule of Income Tax.
02. The undersigned does not bind him to accept the lowest quotation and reserves the right to accept the quotation in whole or in part i.e., with respect to the entire article mentioned in the attached
03. Statement or in respect of one or more than one articles specified in the attached statement as he may decide.
04. On acceptance of the quotation it will become a contract and the contractor shall be bound by the terms and conditions of the quotation as well. Contractor must fulfill the terms and conditions of Government of Bihar as well as govt. of India.
05. The quantity of articles indicated in the attached statement may be increased or decreased at the discretion of the undersigned without assigning any reason.
06. The rates quoted by the contractor shall hold good upto finishing of the renovation works.
07. No amendment will be accepted in the rate of renovation.
08. The description of the said renovation works in details can be had from the office of either RO/Dy. R.O./ARO Bihar Zone- H or from the Principal of DAV Public School, Rotary Campus, Ashok Nagar, Gaya. The payment will be made to the contractor through A/C payee cheque after the finishing of the work and duly approved by the architect.
09. Quotations which do not comply with the above conditions are liable to be rejected.
10. Non-completion of works within the stipulated time, the contractor will be liable to pay penalties as decided by the Building Sub-Committee, except the special circumstances if any.

(Signature)
Principal

Principal
D.A.V. Public School
Rotary Campus, Ashok Nagar
Gaya (Bihar)

ABSTRACT OF COST FOR SLOPE CONSTRUCTION AT DAV PUBLIC SCHOOL, ROTARY CAMPUS, GAYA

S.NO	SoR	AREA OF RAMP PARTICULARS	48 QUANTITY	RATE	SQFT UNIT	AMOUNT
	A	WALL DIMOLITION				
1	14.4.1	Making the opening in brick masonry including dismantling in floor or walls by cutting masonry and making good the damages to walls, flooring and jambs complete, to match existing surface i/c disposal of mulba/ rubbish to the nearest municipal dumping ground, all complete as per direction of Engineer-in-Charge. For door/ window/ clerestory window	1.3		sqm	
	B	SLOPE CONSTRUCTION				
2	11.72	Providing designation 100 A one brick flat soling joints filled with local sand including cost of watering, taxes, royalty all complete as per building specification and direction of E/i	4.5		sqm	
3	2.28	Supplying and Filling in plinth with local sand and under floors including, watering, ramming consolidating and dressing complete.	1.0		cu m	
4	4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering-all work upto plinth level 1:2:4(1 Cement: 2 coarse sand:4 graded stone aggregate 20 mm nominal size)	0.4		Cum	
	C	TILES LAYING				
5	11.21.1.1	Providing and fixing 10 mm thick acid and / or alkali resistant tiles of approved make and colour using acid and / or alkali resisting mortar bedding, and joints filled with acid and / or alkali resisting cement as per IS : 4457, complete as per the direction of Engineer-in-Charge. In flooring on a bed of 10 mm thick mortar 1:4 (1 acid proof cement : 4 coarse sand). Acid and alkali resistant tile.	4.5		Sq m	

	D	IRON GATE				
6	9.48.2	Providing and fixing M.S. grills of required pattern in frames of windows, doors gates etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to openings (Assuming 2.5kg/Sft)	88.0		kg	
7	NA	Painting with ready mixed paint of approved brand and manufacture in all shades to give an even shade. New steel work (two or more coats) Total area of the grill to be	lumsun		Sq.M	
	E	STEEL RAILING				
8	NA	Steel railing of required design on sides	4.8		m	
GRAND TOTAL						

SAY TOTAL COST - Rs