

**TENDER NOTICE**

1	Name of The Works	Renovation of drainage system of old building of the school.
2	Estimated Length	175 sq. feet/53 metres
3	Time of Completion	15 days.
4	Date of Tender Notification	15.09.2023
5	Last Date/Time for Receipt of Bids	18.09.2023
6	Name and Address of office Inviting Tender	Principal, DAV Public School, Rotary Campus, Ashok Nagar, Gaya.
7	Contact Number of Procurement Office	0631-2950279
8	Help Numbers	6205946442

**Following points need attention**

01. The School shall not be liable to pay any tax, freight, etc. which has not been expressly stipulated in the quotation in the event of acceptance of the quotation. The School will deduct TDS as per rule of Income Tax.
02. The undersigned does not bind him to accept the lowest quotation and reserves the right to accept the quotation in whole or in part i.e., with respect to the entire article mentioned in the attached statement or in respect of one or more than one articles specified in the attached statement as he may decide.
03. On acceptance of the quotation it will become a contract and the contractor shall be bound by the terms and conditions of the quotation as well. Contractor must fulfill the terms and conditions of Government of Bihar as well as govt. of India.
04. The quantity of articles indicated in the attached statement may be increased or decreased at the discretion of the undersigned without assigning any reason.
05. The rates quoted by the contractor shall hold good upto finishing of the renovation works. No amendment will be accepted in the rate of renovation.
06. The description of the said renovation works in details can be had from the office of either RO/Dy. R.O./ARO Bihar Zone- H or from the Principal of DAV Public School, Rotary Campus, Ashok Nagar, Gaya. The payment will be made to the contractor through A/C payee cheque after the finishing of the work and duly approved by the architect.
07. Quotations which do not comply with the above conditions are liable to be rejected.
08. Non-completion of works within the stipulated time, the contractor will be liable to pay penalties as decided by the Building Sub-Committee, except the special circumstances if any.

*Lehan*  
14/09/23  
Principal

Principal  
D.A.V. Public School  
Rotary Campus, Ashok Nagar,  
Gaya (Bihar)

Serial	SoR	Particulars	Quantity	Rate	Unit	Amount
		length of pipe work (in feet)	175		feet	
		length of pipe work (in metre)	53		metre	
1	NA	Site preparation and plumbing cost for joining pipeline from toilet to septic tank through all inspection chambers			LUMSUM	
		<b>PIPELINE LAYOUT</b>				
2	NA	Chlorinated Polyvinyl - chloride (CPVC) pipe 6" inner dia.	53		metre	
3	NA	joints and coverings at each pipe connection and IC (considering one pipe being of 3 m and a joint at every 3m along with additional joints along IC, septic tank and toilet outlets)	65		each	
		<b>INSPECTION CHAMBERS (AT 20' INTERVALS)</b>				
4	18.32.1	Constructing masonry Chamber 30x30x50 cm inside, in brick work in cement mortar 1:4 (1 cement :4 coarse sand) for stop cock, with C.L. surface box 100x100 x75 mm (inside) with hinged cover				
		fixed in cement concrete slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), w/ necessary excavation, foundation concrete 1:5:10 ( 1 cement : 5 fine sand : 10 graded stone aggregate 40mm nominal size )				
		and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12mm thick, finished with a floating coat of neat cement complete as per standard design :				
		With common burnt clay F.P.S.(non modular) bricks of class designation 100A	9.0		each	
		with proper water proofing				
		<b>SEPTIK TANK</b>				
5	NA	2000L capacity Ready made septic tanks with proper sewerage connections			LUMSUM	