


TENDER NOTICE

Ref. No. DAV/RC,AN/GAYA/2025/369

Dated 04/01/2025

1	Name of The Works	Painting of all blocks and compound wall with repair of DAV Public School, Rotary Campus.
2	Estimated Area	1. Exterior painting of compound wall – 17943 SFT 2. Interior painting i) Wall & ceiling painting: 102548.37 SFT ii) Dado Painting : 13293.29 SFT MS Grill, window, : 10838.56 SFT doors etc. panting iii) Wood work painting : 5301.65 SFT
3	Time of Completion	60 days from issue of work order
4	Date of Tender Notification	04/01/2025
5	Last Date/Time for Receipt of Bids	14/01/2025 (upto 2.00 pm)
6	Name and Address of office Inviting Tender	Principal, DAV Public School, Rotary Campus, Ashok Nagar, Gaya.
7	Contact Number of Procurement Office	0631-2950279
8	Help Numbers	9425835417

1. The School shall not be liable to pay any tax, freight, etc. which has not been expressly stipulated in the quotation in the event of acceptance of the quotation. The School will deduct TDS as per rule of Income Tax.
2. The undersigned does not bind him to accept the lowest quotation and reserves the right to accept the quotation in whole or in part i.e., with respect to the entire article mentioned in the attached statement or in respect of one or more than one articles specified in the attached statement as he may decide.
3. On acceptance of the quotation it will become a contract and the contractor shall be bound by the terms and conditions of the quotation as well. Contractor must fulfill the terms and conditions of Government of Bihar as well as govt. of India.
4. The quantity of articles indicated in the attached statement may be increased or decreased at the discretion of the undersigned without assigning any reason.
5. The rates quoted by the contractor shall hold good upto finishing of the renovation works. No amendment will be accepted in the rate of renovation.
6. The description of the said renovation works in details can be had from the office of either RO/Dy. R.O./ARO Bihar Zone- H or from the Principal of DAV Public School, Rotary Campus, Ashok Nagar, Gaya. The payment will be made to the contractor through A/C payee cheque after the finishing of the work and duly approved by the architect.
7. Quotations which do not comply with the above conditions are liable to be rejected.
8. Non-completion of works within the stipulated time, the contractor will be liable to pay penalties as decided by the Building Sub-Committee, except the special circumstances if any.
9. Please submit the quotation clearly mention the name of the work on top of the envelop


(PRINCIPAL)
D.A.V. Public School
Rotary Campus, Ashok Naga
Gaya (Bihar)

ABSTRACT OF COST OF INTERIOR PAINTING OF ALL BLOCKS AND COMPOUND WALL WORK

D.A.V. PUBLIC SCHOOL, ROTARY CAMPUS, AHEAD OF MEDICAL COLLEGE, GAYA, BIHAR.

Sl.No.	S.O.R.	DESCRIPTION	Qty.	Unit.
(A) EXTERIOR PAINTING				
(1) COMPOUND WALL				
		i. Area of exterior painting = 17943 Sft (1667.57 Sqm)		
SECTION- I (FINISHING WORK)				
1	14.67	Finishing walls with Premium Acrylic smooth exterior paint with Silicone additives of required shade. (with Asian paints)		
	14.67.1	Old work(Two or more coat applied@ 1.43 ltr/10sqm over existing cement paint surface	1667.57	Sqm
2	13.74	Removing white or colour wash by scrapping and sand paper in and preparing the surface smooth including necessary repair scratches etc. complete.	1667.57	Sqm
TOTAL				
ROUNDUP				
Cost of exterior painting per sqft.				
(B) INTERIOR PAINTING -All Blocks, Security Room & Store room				
1. WALL AND CEILING PAINTING				
		i. Area of painting at all floors (Ground+1st +2nd +head room)= 102548.37 Sft(9530.52 Sqm)		
SECTION- I (FINISHING WORK)				
1	13.81A	Distempering with 1st quality acrylic distemper, having VOC (Volatile Organic Compound) content less than 50 grams/litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour.		
	13.81.2B	Two coats	9530.52	Sqm
TOTAL				
ROUNDUP				
Cost of Painting per S.Ft.				
2. DADO PAINTING IN CLASS ROOMS.				
		i. Area of painting at all floors = 13293.29 Sft (1235.44 Sqm)		
SECTION- I (FINISHING WORK)				
1	13.48	Finishing with Delux Multi surface paint system for interiors and exteriors as per manufacturers specifications.		
	-13.78.1			
	13.48.1	Two or more coats applied on walls @ 1.25 ltr/10 sqm	1235.44	Sqm
TOTAL				

ROUNDUP

Cost of Painting per S.Ft.

3. STEEL WINDOWS, GRILLS , DOORS & COLLAPSIBLE GATE, GATE ETC. PAINTING

i. Area of painting at all floors & Compound = 10838.56 Sft (1007.30 Sqm)

SECTION- I (FINISHING WORK)

1 13.82 Painting with ready mixed paint of approved brand and manufacture in all shades to give an even shade:

13.82.3 Old steel work (one or more coats) 1007.30 Sqm

TOTAL

ROUNDUP

Cost of Painting per S.Ft.

4. WOOD WORK PAINTING

i. Area of painting at all floors = 5301.65 Sft (492.72Sqm)

SECTION- I (FINISHING WORK)

1 13.82 Painting with ready mixed paint of approved brand and manufacture in all shades to give an even shade:

13.82.4 Old wood work (one or more coats) 492.72 Sqm