

TENDER NOTICE

1	Name of The Works	Repair and finishing up of ceiling of damage roof, beam, Chhajja and Column of school building.
2	Estimated Area	As per estimate made by Architect. (Attached Estimate)
3	Time of Completion	02 Months
4	Date of Tender Notification	11 .01.2023
5	Last Date/Time for Receipt of Bids	18 .01.2023
6	Name and Address of office Inviting Tender	Principal, DAV Public School, Rotary Campus, Ashok Nagar, Gaya.
7	Contact Number of Procurement Office	0631-2950279
8	Help Numbers	6205946442

Following points need attention

1. The School shall not be liable to pay any tax, freight, etc. which has not been expressly stipulated in the quotation in the event of acceptance of the quotation. The School will deduct TDS as per rule of Income Tax.
2. The undersigned does not bind him to accept the lowest quotation and reserves the right to accept the quotation in whole or in part i.e., with respect to the entire article mentioned in the attached statement or in respect of one or more than one articles specified in the attached statement as he may decide.
3. On acceptance of the quotation it will become a contract and the contractor shall be bound by the terms and conditions of the quotation as well. Contractor must fulfill the terms and conditions of Government of Bihar as well as govt. of India.
4. The quantity of articles indicated in the attached statement may be increased or decreased at the discretion of the undersigned without assigning any reason.
5. The rates quoted by the contractor shall hold good upto finishing of the renovation works. No amendment will be accepted in the rate of renovation.
6. The description of the said renovation works in details can be had from the office of either RO/Dy. R.O./ARO Bihar Zone- H or from the Principal of DAV Public School, Rotary Campus, Ashok Nagar, Gaya. The payment will be made to the contractor through A/C payee cheque after the finishing of the work and duly approved by the architect.
7. Quotations which do not comply with the above conditions are liable to be rejected.
8. Non-completion of works within the stipulated time, the contractor will be liable to pay penalties as decided by the Building Sub-Committee, except the special circumstances if any.

11/01/23
Principal
Principal
D.A.V. Public School
Rotary Campus, Ashok Nagar
Gaya (Bihar)

ABSTRACT OF COST FOR REPAIR AND FINISHING UP OF CEILING AT - DAV PUBLIC SCHOOL, ROTARY CAMPUS

Serial	SoR	Particulars	Quantity	Rate	Unit	Amount
		area for repair	15,000.0		sqft	
1	15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	1,394.0		sqm	
2	13.30.1	Rough cast plaster upto 10m night above ground level with a mixture of sand and gravel or crushed stone from 6 mm to 10 mm nominal size dashed over and including the fresh plaster in two layers,				
		under layer 12 mm cement plaster 1:4(1 cement :4 coarse sand) and top layer 10 mm cement plaster 1:3 (1 cement :3 coarse sand) mixed with 10% finely grounded hydrated lime by volume of cement: Ordinary cement finish using ordinary cement	1394.0		sqm	
3	13.36.5	Extra for providing and mixing water proofing material in proportion recommended by the manufacturers: 20 mm cement plaster 1:3(1 cement:3 sand)	1394.0		sqm	
4	14.72	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube	1394.0		Sq m	
			Total			

--

NOTE

Rates are inclusive of G.S.T.

Painting cost is not included in this estimate as new estimate of complete painting will be prepared separately

Ceiling area includes major portions of 2nd floor ceiling (sloped and plane) and minor areas of ground, 1st and 2nd floor as well. This comes to approximately 15000 sqft